



Address all correspondence to the Municipal Manager

REQUEST FOR QUOTATION

Date: 24 JULY 2019

SUPPLY AND INSTALLATION OF THE BULK/MEDIUM VOLTAGE VERIFICATION METERS AT THE MUNICIPAL MAIN SUBSTATIONS (PHASE 1)

Quotations are hereby invited from the accredited services providers for the Supply and Installation of the bulk/medium voltage verification meters at the Municipal Main Substations (Phase 1)

The 80\20 preference point system will be used when evaluating the quotation, which is in terms of PPPFA and the SCM policy of the municipality.

The specifications are as follows:

BALFOUR MAIN SUBSTATION:

Incomer 1:

TYPE: 1 x Elster CT (Current Transformer) Meters

MODEL : A1700

CT RATIO : 600/5A

VT RATIO : 6.6KV/110V

Incomer 2:

TYPE: 1 x Elster CT (Current Transformer) Meters

MODEL : A1700

CT RATIO : 400/5A

VT RATIO : 6.6KV/110V

GREYLINGSTAD MAIN SUBSTATION:

TYPE: 1 x Elster CT (Current Transformer) Meters

MODEL : A1700

CT RATIO : 300/5A

VT RATIO : 11KV/110V

GROOTVLEI MAIN SUBSTATION:

1 x Distribution Box, Size: H:600mm x W:600mm x D:200mm

TYPE : 1 x Elster CT (Current Transformer) Meters

MODEL: A1700

OUTDOOR TYPE : 6.6 KV Pole Mounted CT. VT Metering Unit

Nominal Voltage Un: 6.6KV

Highest System Voltage Um :7.2KV

Lighthing Impulse (BIL) : 60KV

Power Frequency Dry (60s) :20KV

Specification : IEC 60044-1

Insulation Medium : Paper/Oil

Bushing/ Creepage : 31(Very Heavy Pollution) mm/KVA

Terminals : M12 x 25mm

Voltage Ratio: 6.6KV/110V

Current Ratio : 400/5A

Service providers must be registered with the Central Supplier Database www.csd.gov.za for their quotations to be considered.


PRE-QUALIFICATION FOR PREFERENTIAL PROCUREMENT (PPPFA 05 of 2017)

- EXEMPTED MICRO ENTERPRISE OR QUALIFYING SMALL ENTERPRISE WITHIN THE JURISDICTION OF DIPALESENG WILL BE GIVEN FIRST PREFERENCE.
- BBB-EE CERTIFICATE & DECLARATION OF INTEREST SHOULD ACCOMPANY THE QUOTATION.

Duly completed RFQ's must be sealed in an envelope clearly marked: **MUNICIPAL MANAGER, DIPALESENG LOCAL MUNICIPALITY "SUPPLY AND INSTALLATION OF THE BULK/MEDIUM VOLTAGE VERIFICATION METERS AT THE MUNICIPAL MAIN SUBSTATIONS (PHASE 1)"** must be placed in the tender box at Dipaleseng Local Municipality's offices, Cnr Johnny Mokoena Drive & Themba Shozi Street in Balfour, not later than 12H00 on **31 JULY 2019**.

Late submission will not be accepted and Dipaleseng Local Municipality does not bind itself to accept the lowest or any submitted quotation. Dipaleseng Local Municipality reserves the right to accept a quotation as a whole or in part.

For enquiry contact **Mr Peter Makhene** on **072 854 0103** or **Ms Mashiane** on **071 282 9446**


MR IP MUTSHINYALI
MUNICIPAL MANAGER